AD	
AD	



REPORT NO. 5059B

MM&TE - APPLICATION OF RADAR TO BALLISTIC ACCEPTANCE TESTING OF AMMUNITION (ARBAT) PHASE B: ANTENNA DEVELOPMENT/FABRICATION

FINAL REPORT (PHASE B)

CDRL: A002



30 September 1976

SARPA-QA-A-R

PICATINNY ARSENAL DOVER, NEW JERSEY 07801

DRCMS CODE: 4932.05.4139.1

CONTRACT NO. DAAA21-73-C-0664

4932.05.4139.1

Distribution of the document is unlimited.

The findings in this report are not to be construed as an official Department of Army position.

Destroy this report when no longer needed. Do not return it to the originator.

ITT GILFILLAN 7821 Orion Avenue Van Nuys, California 90406 9970722 018

MUTERNATION STATEMENT A

Sparond for public minoral

Desirientian Bulkraited



International Telephone and Telegraph Corporation

ITT Gilfillan

Defense-Space Group

7821 Orion Avenue, P.O. Box 7713 Van Nuys, California 91409 Telephone (213)988-2600 Telex 651421 • TWX 910-495-1787

November 8, 1976 In Reply Refer To: 297/5059/94/ASO

Department of the Army Headquarters, Picatinny Arsenal Dover, New Jersey 07801

Attention: Code SARPA-QA-A-R

Subject:

Contract DAAA21-73-C-0664

Data Item A002 - Final Technical Report

for Mfg. Methods & Technology: Application of Radar to

Ballistic Acceptance Testing of Ammunition (ARBAT)

AMCMS Code 4932.05.4139.1

Gentlemen:

In accordance with CLIN 0002 of the subject contract, ITT Gilfillan is herewith submitting the Final Technical Report for the ARBAT Phase "B" Program to the Appendix B Report Distribution List as required.

The document incorporates all comments and modifications to the draft report previously submitted to you, and its submittal hereby completes the requirements of the subject contract.

If there are any further inquiries regarding this report, please contact the undersigned.

Very truly yours,

A. S. Ostrom

Sr. Contract Administrator

ASO:pk

Enclosure: a/s

Distribution: See Attached Sheet

cc: DCAS/VN, Attn: W. W. Sodeman (w/o encl.)

DCAS/VN, Attn: O. D. North (w/o encl.)

ABSTRACT

The ARBAT (Application of Radar to Ballistic Acceptance Testing of Ammunition) radar system is presently being developed by Picatinny Arsenal for range instrumentation purposes. This report covers the development of the antenna subsystem through range testing of a 9-element test array and assembly of the full antenna. The subject antenna is a 10×12 ft phase/frequency/mechanical scanning X-band planar array. Elevation scanning is by means of phase variation obtained by program controlled 4-bit diode phase shifters. In addition to the electronic scanning capability, a manual tilt capability is included to accommodate range terrain variations. Azimuth scanning is accomplished by frequency variation, and limited mechanical rotation of the array by servo control. Mechanical rotation is limited to ± 170 degrees which fulfills the requirements of the application. The transmitter/receiver unit is mounted on the antenna back structure. Connections to and from the transmitter/receiver and phase shifter control electronics are made through a "windup" cable arrangement eliminating the need for slip rings. The array is made up of 167 horizontal dual-slot pair radiators fed by a vertical feed line.

The antenna incorporates a performance monitoring feature which functions as a confidence indicator and as a means for fault location down to the single horizontal array level. This feature is implemented by means of coupling each horizontal array, opposite the feed end, to a vertical combiner, or performance monitor line. Residual RF energy in the radiating sections is combined and detected to monitor array performance. Simple diagnostic phase shifter exercising programs facilitate fault location.

TABLE OF CONTENTS

Section				Page
	ABST	RACT		iii
	FORE	CWORD		v
1.	DEVE	CLOPMEN	T APPROACH	1
	1. I	Overall	Characteristics	1
		1.1.1	General Description	1
	1.2	Detailed	d Requirements	9
2.	DESI	GN DESCE	RIPTIONS	18
	2.1 2.2 2.3 2.4	Vertica	ructure ntal Array Waveguide Sections l Feed Line ree Twist Crossguide Coupler Section	19 24 35 40
		2.4.1	Load: Termination (Vertical Feed Coupler) Phase Randomization Blocks	44 46
	2.5 2.6		Phase Shifter Antenna Performance Monitor Concept	51 54
			Performance Monitor Line Loads: Performance Monitor Line	56 61
3.	TEST	PROGRA	AM	63
	3.1 3.2		rray (3 Section) Tests lement Test Array	63 68
		3.2.1	Test Patterns	69
4.	SUMI	MARY OF	TEST RESULTS	82
	APPI	ENDIX A		83
	REPO	ORT DIST	RIBUTION	105
	REDA	ORT DOC	IMENTATION PAGE	109

LIST OF ILLUSTRATIONS

Figure		Page
1.	ARBAT Phase Antenna Development Sequence	2
2.	System Configuration Concept	4
3.	Back Structure/Transceiver Mounting	5
4.	Antenna Signal Flow Graphic Schematic	6
5.	Antenna Assembly Front Array View	7
6.	Antenna Assembly Rear View	8
7.	Back Structure Truss Elements	21
8.	Back Structure/Transceiver Mounting	22
9.	Computer Deflection Analysis	2 3
10.	Insertion Phase Measurement/Comparison Test Setup	26
11.	Insertion Phase Plot (After Etching Process)	27
12.	Phase Error Plot (2nd Aperture Excitation at 9.3 GHz)	29
13.	Phase Error Plot (2nd Aperture Excitation at 9.65 GHz)	30
14.	Phase Error Plot (3rd Aperture Excitation at 10 GHz)	31
15.	Amplitude Plot (1st Aperture Excitation at 9.65 GHz)	32
16.	Amplitude Plot (2nd Aperture Excitation at 9.3 GHz)	33
17.	Amplitude Plot (3rd Aperture Excitation at 20 GHz)	34
18.	Vertical Line Feed in Assembled Antenna	36
19.	Vertical Line Feed Insertion Loss vs Frequency	37
20.	VSWR vs Frequency: Line Feed Section #3	38
21.	VSWR vs Frequency: Line Feed Section #3 (Expanded	2.0
2.2	Scale)	39
22.	Ninety Degree Twist Crossguid Coupler in Assembled Antenna	41
23.	Ninety Degree Twist Crossguide Section	42
24.	Ninety Degree Twist Section VSWR Plot	43
25.	Load: Vertical Feed Coupler VSWR Plot	45
26.	Phase Randomization Block Location in Coupler	47
27.	Phase Randomization Block Series	48
28.	Phase Randomization Block	49
29.	Phase Randomization Block	50
30.	Phase Shifter Decode Logic Organization	52
31.	Phase Shifter Position in Assembled Antenna	53
32.	Performance Monitoring Concept	55
33.	Performance Monitor Slot Dimensions	57
34.	Slot Coupling Values	58
35.	Performance Monitor Line in Assembled Antenna	59
36.	Performance Monitor Line (Close-Up View)	60
37	Load Block VSWR Measurement	62

LIST OF ILLUSTRATIONS (Continued)

Figure		Page
38.	Horizontal Array Element Insertion Loss (Dual Slot	
30.	Radiators)	64
39.	Horizontal Array Element Return Loss (Dual Slot	
, .	Radiators)	65
40.	D-2 Horizontal Array Element Return Loss	
	(Expanded D2 RL)	66
41.	Predicted Pattern (3 Element Test)	67
42.	Nine-Element Test Array Assembly	69
43.	Nine-Element Test Array Assembled	70
44.	Nine-Element Test Array Elevation Scan	71
45.	ARBAT 9-Element Test Array Pattern (9.30)	72
46.	ARBAT 9-Element Test Array Pattern (9.65)	73
47.	ARBAT 9-Element Test Array Pattern (10.0)	74
48.	ARBAT 9-Element Test Array Pattern (9.3)	75
49.	ARBAT 9-Element Test Array Pattern (9.65)	76
50.	ARBAT 9-Element Test Array Pattern (10.0)	77
51.	ARBAT 9-Element Test Array Pattern (9.3)	78
52.	ARBAT 9-Element Test Array Pattern (9.65)	79
53.	ARBAT 9-Element Test Array Pattern (10.0)	80
54	ARBAT 9-Element Test Array Pattern (9.65)	81

ARBAT ANTENNA

1. DEVELOPMENT APPROACH

The ARBAT system required the development of an antenna to meet the unique performance requirements of ballistic ammunition testing. The approach followed for this development was standard in antenna design; a paper design was first generated by means of computer analyses. Input data for these analyses were based on proven design parameters generated for similar antennas produced for other programs. An iterative process, in which a single element followed by multiple horizontal array elements were fabricated, tested and modified as necessary to optimize configuration, was followed. A detailed illustration of the development/fabrication sequence followed with the ARBAT antenna is shown in Figure 1.

1.1 Overall Characteristics

1.1.1 General Description. - The antenna is a planar array design with an aperture of 10 ft x 12 ft. Beam scanning is accomplished by a combination of electronic and mechanical means. The beam is scanned in elevation by four-bit diode phase shifters (GFE), whereas azimuth scanning is by frequency variation and mechanical rotation of the array. The mechanical rotation capability is limited to a maximum of ± 170 degrees which fulfills the requirements in ammunition testing applications. Provisions are included in the antenna back structure design for a mechnical adjustment (tilt) of 0 to 25 degrees in elevation. The back structure is designed to support the microwave assembly, phase shifter power supplies and logic, and the transmitter/receiver unit. In view of the less than 360 degree rotation required (±170°), a cable "windup" scheme is used for power and all input/output lines to and from the antenna which obviates the need for slip rings. The artists sketch in Figure 2 illustrates the overall system configuration concept. A more detailed view illustrating the back structure concept is shown in Figure 3. The array contains 167 dual slot horizontal radiators which are fed by a single vertical feed line via 90-degree waveguide twist and offset sections followed by 4-bit diode phase shifters. arrays terminate at a vertical performance monitor line at the end opposite the feed line. The performance monitor line is a part of the performance monitor and fault location feature incorporated in the system design. Antenna performance determination is accomplished by the measurement of residual RF energy at the extreme ends of the horizontal arrays (opposite the feed ends). Coupling from the vertical feed line to the arrays and from the arrays to the performance monitor line is by 4-port coupler




Figure 1. ARBAT Phase Antenna Development Sequence

NOTES TO FIGURE 1

NOTE 1:

Fabrication of ''dummy'' phase shifter waveguide sections with Rexolite phase shifting block inserts for substitution in place of the diode phase shifters which were not available at the time the tests were required. The Rexolite blocks provide a step transformer with a maximum VSWR of 1.1:5. The phase shift increments of the Rexolite block/waveguide section units were adjusted to ±3 degrees by the application of dielectric tape directly to the side of the block; phase shift was then measured at center frequency.

NOTE 2:

A nine element test array was assembled using the array elements, short feed, waveguide twist sections, dummy phase shifter blocks and couplers prepared earlier. These elements were assembled into a test support to simulate the final full array configuration except with a reduced number of array elements. This test assembly was then moved to the test range for the tests described later in this report.




Figure 2. System Configuration Concept




Figure 3. Back Structure/Transceiver Mounting

sections. Coupling sections at the feed end contain end loads and phase randomization blocks. The 4-port couplers at the performance monitor line section are designed with a common flange which mates with the individual flanges at the output ends of each horizontal array element. The performance monitor feature is implemented by terminating the lower end of the vertical performance monitor line section with a crystal video detector whose output is routed via coaxial cable to the monitoring circuitry. A pictorial drawing showing microwave element configuration and signal flow illustrates the basic antenna physical design, Figure 4.

The two photographs following show the assembled antenna microwave section. The front side showing the horizontal array elements, Figure 5; and the rear of the assembly showing back structure details, vertical feed line, 90 degree twist waveguide sections, and phase shifters is shown in Figure 6.




Figure 4. Antenna Signal Flow Graphic Schematic




Figure 5. Antenna Assembly Front Array View




Figure 6. Antenna Assembly Rear View

1.2 Detailed Requirements

The following extracts from Appendix A of the contract Statement of Work, include the basic performance requirements placed on the antenna to be achieved when mounted on a suitable pedestal with servo control and when coupled to the modified GFE transmitter for which the antenna has been designed. Pedestal assembly and transceiver modifications are parts of forthcoming program phases.

- 1.0 Beam Steering
- 1.1 Electrical
- 1.1.1 Azimuth: 7.7 degrees minimum
- 1.1.2 Elevation: ±35 degrees minimum
- 1.2 Mechanical
- 1.2.1 Azimuth: ±170 degrees rotation minimum at 40 degrees/ sec² while maintaining pointing accuracy during rotation.

The electrical beam motion shall be accomplished with diode phase shifters in elevation and with frequency scanned slotted waveguide radiators in azimuth. The antenna shall be designed for electrical sequential lobing. Provision shall be made for a mechanical adjustment capability in elevation. The angle between the horizontal position and the beam normal of the antenna shall have an adjustable range of 0 to 25°.

2.0	Electrical Requ	irements		
2.1	Detailed Specification			
2.1.1	Frequency Band	X - E		
2.1.2	Center Frequen	acy - See Note 1		
2.1.3	Bandwidth for B	Frequency Scan - See	Note I	
2.1.4	Azimuth Scan (I	Electrical): 7.70		
2.1.5	Elevation Scan	(Electrical): ±35°		
2.1.6	Bandwidth, 3 dl	B (Note 2)		
	Azimuth	for 0° elevation for ±35° elevation	.55° .	
	Elevation	for 0° elevation for $\pm 35^{\circ}$ elevation	.66° .81°	
2.1.7	Beam Pointing	Error, Electrical		
	Elevation		.37 mrad	
2.1.8	Electronic Bear in Elevation	m Switching Time	1.0 MHz	
2 1 0	Polarization		Horizontal	

NOTE 1: As stated in antenna design specification. (Contract DAAA21-72-C-0725)

2.1.10 Sidelobe Level (Note 2)

Azimuth	at 0 ⁰ elev. scan at ±35 ⁰ elev. scan	-25 dB -23 dB
Elevation	at 0° elev. scan	-25 dB -23 dB

2.1.11 Terminal Gain at 0° Elev. scan at Center Frequency

46.0 minimum (Note 3)

Terminal Gain at ±35° Elev. scan at Center Frequency

45.0 dB (Note 3)

2.1.12 Power Capability

peak 30 kw average 300 w

2.2 Major Subassemblies

- 2.2.1 For description and characteristics of GFE phase shifters see Picatinny Arsenal Document Technical Description TDPA-QAAR-2340.
- 2.3 Techniques Used
- 2.3.1 Wideband Operation for Frequency Scan

Appropriate techniques shall be applied to suppress the grating lobes and improve the radiation pattern while operating over the maximum bandwidth necessary for the frequency scan in azimuth.

2.3.2 Phase Randomization

To avoid the quantization error of the 4-bit phase shifter and the associated increase in sidelobe level, an appropriate phase randomization technique shall be used for each element of the horizontal array. The antenna buffer shall be able to compensate for this additional insertion phase.

NOTE 2: These parameters will be achieved at the center frequency.

NOTE 3: Based on an average phase shifter insertion loss of 2.5 dB.

2.3.3 Signal Coupling

To generate an optimum pencil beam with the most efficient low sidelobe pattern, proper weighting (30 dB Taylor excitation (N=4)) shall be applied by specifying appropriate coupling apertures from the vertical feed to the horizontal arrays and in establishing the slots in the horizontal elements.

2.3.4 CW Mode

The requirements for a CW mode of operation, to be added in the future, should be considered during the fabrication and design modifications of the antenna.

- 2.3 Mechanical Requirements
- 2.3.1 General Mechanical Requirements
- 2.3.1.1 The antenna array and its supporting structure shall be of sufficient rigidity and strength to minimize the deflection when subjected to the required acceleration and wind loading. When assembled on an appropriate servo mount pedestal (AN/SPS-48 or equivalent) and when subjected simultaneously to $40^{\circ}/\text{sec}^2$ acceleration in azimuth and 20 mph wind load, the antenna system shall exhibit no more than the following maximum deflection of the beam:

BASIC ANTENNA ANTENNA + PEDESTAL (PHASE B) + VEHICLE (PHASE C)

- a. Azimuth .377 mrad max. .660 mrad max.
- b. Elevation .184 mrad max. .690 mrad max.
- 2.3.1.2 The antenna shall be properly designed, fabricated and assembled to permit electrical and mechanical operation in accordance with this and the complete ARBAT radar system specifications when subjected to the environmental conditions specified in paragraph 2.8.

In a non-operative state, the antenna system shall be sufficiently rugged to withstand, without damage, vibration and shock during transportation per paragraphs 2.7 and 2.8, and wind loads and precipitation per paragraph 2.8.

- 2.3.2 Detailed Mechanical Specifications
- 2.3.2.1 Antenna Aperture Size: Height 120 ins. Width 144 ins.
- 2.3.2.2 Total Antenna Width 154 ins. (ref)
- 2.3.2.3 Adjustable Elevation Tilt 0 to 25°
- 2.3.2.4 Mechanical Pointing Accuracy (deflection error due to all loading, see para 2.3.1.1) az .377 mrad max.
- 2.3.2.5 Maximum Weight (Antenna, transceiver, buffer, power supplies, cables) without pedestal 1700 lbs. max
- 2.3.3 Antenna Microwave Hardware

The antenna shall include, but not be limited to, the following microwave hardware:

- 2.3.3.1 Vertical Feed Line
- 2.3.3.2 90° Waveguide Twist (167)
- 2.3.3.3 Diode Phase Shifters (167)
- 2.3.3.4 Mounting Plate(s) for Phase Shifters
- 2.3.3.5 Horizontal Slotted Array Element (167)
- 2.3.3.6 Required coupling Elements, straight and angular (167 each)
- 2.3.4 Mechanical Mounting Structure

The microwave elements shall be securely mounted to a back structure.

2.3.5 Protective Enclosures

- 2.3.5.1 A protective enclosure (cover) shall be provided for the phase shifters.
- 2.3.5.2 Weather-resistant, electrically non-interfering plastic tape (tedlar-mylar or equivalent) shall cover the antenna radiating slots and prevent entrance and accumulation of water, sand and dust in the microwave elements.
- 2.3.5.3 The contractor shall supply a waterproof, soft plastic or coated or impregnated cloth hood to protect the antenna while not operated or while in storage.

2.3.6 Protective Finishes

The exterior surfaces of the antenna system (wave-guides, mounting structure, enclosures, transceiver) shall be covered with protective coating. The color shall be silver or white, to minimize the heating due to solar radiation. The interior surfaces shall have appropriate corrosion-resistant finish.

2.3.7 Material Compatibility

Different materials in contact with each other shall be chosen with careful regard to the electrochemical series so that they are compatible and will not corrode because of electrical potential differences.

2.4 Testing

The contractor shall perform the following tests:

- 2.4.1 Laboratory tests for microwave components (vertical feed, horizontal array elements, etc).
- 2.4.2 Laboratory and range tests for the 9-element test array.

2.5 Calibration

All instrumentation used for laboratory and range testing shall be properly calibrated with standards traceable to the National Bureau of Standards.

2.6 Maintenance

For ease of maintenance, electrical and microwave components shall be mounted so as to permit field testing and replacement by qualified personnel.

2.7 Mobility/Transportability

- 2.7.1 In the next phase (C), the antenna system will be mounted on a servo pedestal located on an antenna vehicle. The vehicle will be transported by public highways and/or railroads between proving grounds. Within the proving grounds, graded, light duty, hard surface roads will be used. However, the system shall be capable of being moved at low speeds (5 mph) on unimproved dirt roads. The antenna system shall be able to withstand, without damage, the above transportation requirements.
- 2.7.2 During transportation within the proving grounds the overall system height shall be less than 16 feet, 12 feet desired. If it is necessary to lower the antenna to meet this requirement, the lowering mechanism shall be self-contained and hydraulically or hand operated. The width of the system during transportation shall not exceed 8 feet. When moving from site to site within the proving grounds, a maximum set-up time of 8 hours is required, four hours desired.
- 2.7.3 For transportation between proving grounds, it shall be possible to deploy the system into a configuration transportable over public roads and compatible with applicable federal, state and local regulations. If necessary, subsystem may be removed or lowered from the main assembly with the aid of a crane (to be provided by Proving Grounds).

2.8 Environmental Requirements

2.8.1 Temperature

The antenna system shall be capable of operating in an ambient air temperature range of $-65^{\circ}\mathrm{F}$ to $+165^{\circ}\mathrm{F}$ and maintaining the accuracy requirements specified in section 2 for an ambient air temperature range of $-20^{\circ}\mathrm{F}$ to $+120^{\circ}\mathrm{F}$.

2.8.2 Wind

The antenna system shall be capable of operating and maintaining the accuracy requirements specified in section 2 in winds up to 30 mph. In addition, when the antenna is secured and not operating, it shall be capable of withstanding winds up to 75 mph.

2.8.3 Precipitation (Rain, Snow, Hail, Ice)

The antenna system shall be properly designed and fabricated to prevent limitation in accuracy and operational capability caused by internal leakage and accumulation of precipitation. The effects of external accumulation should be kept as low as possible by proper design.

2.8.4 Humidity

The antenna system shall be properly designed and fabricated to prevent deterioration of system performance due to humidity encountered in the continental United States.

2.8.5 Sand and Dust

The antenna system shall be properly designed and fabricated to prevent sand and dust particles from entering the interior of the system, accumulating there and causing electrical and/or mechanical interference.

2.8.6 Solar Radiation

The antenna system shall be designed to operate under extreme environmental conditions with a solar load of 360 BTU per square foot per hour taken at the worst orientation of the sun relative to the equipment. To limit the heating effect, the antenna system shall have an exterior reflective color of silver or white.

2.8.7 Shock

The antenna system, when properly mounted on servo pedestal and antenna vehicle, shall be able to withstand the effects of a 10g shock environment (any direction)

during transit by truck. The equipment shall be designed to withstand humping loads common to rail transportation.

2.9 Reliability

The reliability of the antenna system shall be sufficiently high to permit achievement of the desired objective:

MTBF for the entire radar system - 200 hours.

2. DESIGN DESCRIPTIONS

The following sub-sections provide brief descriptions of the major components in the ARBAT antenna design. Detailed physical descriptions are generally not included in this section, except that in some instances basic dimensions are included on sketches to provide the reader with sufficient information to facilitate visualization of the component described.

Test results for critical parameters are included for those components where such tests are applicable.

Drawings for the antenna are packaged separately from this report (3 copies supplied to Picatinny Arsenal and requests for copies should be made there).

The following drawings are available at Picatinny Arsenal.

	Drawing	Component/Assembly
1.	140300-1	Antenna Assy, ARBAT
2.	140301-1	Back Structure, Antenna
3.	140311-1	Twist, 90°, W/G
4.	140309-2	Array Assy, W/G
5.	140309-2	Parts List
6.	140312-1	Flange
7.	140312-2	Flange
8.	140307-1	Feed Line
9.	140313-1	Load Assy
10.	140310-1	Comb
11.	140310-2	Comb
12.	140317-1	Comb
13.	140317-2	Comb
14.	140315-1	Structure
15.	140328-1	Bracket
16.	140328-2	Bracket

	Drawing	Component/Assembly	
17.	140316-1	Panel	
18.	140318-1	Bracket	
19.	140319-1	Block	
20.	140320-1	Retainer	
21.	140308-1	Monitor	
22.	140325-1	Load	
23.	140321-1	Cover	
24.	140322-1	Cover	
25.	140323-1	Cover	
26.	140324-1	Angle	
27.	140302-1	Support	
28.	140303-1	Support	
29.	140304-1	Support	
30.	140304-2	Support	
31.	140305-1	Base	
32.	140306-1	Clevis	
33.	140326-1	Rod End	
34.	140327-1	Clevis	

2.1 Back Structure

The antenna back structure is a rigid welded aluminum (6061-T6) structure designed to support the microwave elements of the antenna with the associated phase shifter drive electronics and the transmitter/receiver. The structure is designed for mounting on a rotating pedestal which will provide the mechanical portion of the required beam scanning capability. A non-scalar structural schematic sketch is used for clarity in Figure 7 to illustrate the basic construction of the back support.

A full view, artists sketch, of the backside of the antenna with the transmitter/receiver mounted shows the position of the transceiver/mounting, Figure 8.

The measured weight of the completed back structure is 722.0 pounds which includes the array positioning combs.

The obvious prime requirement for the back structure is rigidity and desirably the rigidity should be achieved with reasonably light-weight. Computer defelection analysis results are shown in Figure 9.

The mechanical structure analysis for the total antenna structure is contained in Appendix A.




Figure 7. Back Structure Truss Elements

6005-6






Figure 8. Back Structure/Transceiver Mounting

PREPARED	NAME P. ZAE	7/25/73	ITT Gilfillan Inc.	SHEET 13 OF
CHECKED			COMPUTER MODEL FOR	SKETCH NO. PHASE 13
APPROVED			STRUPAK ANALYSIS	THASE &





ASSUME CENTER SECTION TORQUE BOX TO

BE RIGHT & DEFLECTIONS ARE DUE TO BENDING

DF TRUSS STRUCTURE ONLY




Figure 9. Computer Deflection Analysis

2.2 Horizontal Array Waveguide Sections

The radiating elements in the ARBAT antenna are horizontal array waveguide sections. Radiation is via dual pairs of slots milled in the narrow dimension side. Array waveguide sections are fabricated from thin wall precision waveguide made from 6061-T6 aluminum alloy conforming to MIL-W-85/6 requirements. This waveguide is 0.400 by 0.750 inches inside and 0.476 by 0.826 inches outside. Each array section is 145.86 inches in length and contain 161 dual slot pairs (322 milled slots) in the narrow dimension radiating edge. Each individual array section is fitted with a flange at each end for mating with a diode phase shifter at the feed end and with a coupler flange plate at the opposite or performance monitor end. The flanges are welded at each corner to the mating waveguide and the remaining area of contact is then sealed.

Before assembly of the horizontal array sections, the slotted side is covered with a multi-layer RF transparent tape (G. T. Schjeldahl Co., Type G. 133500-014) and all surfaces are eventually painted with white epoxy paint.

Horizontal Array Section Test Data. - The following data represents the individual element test results obtained for finalized configurations. Consequently, the results presented represent the established requirements for which the production samples were later tested. This data is generally presented in one of two forms, tabular or graphic and in all instances the data is self explanatory. The following specific data is contained in this section:

- a. Insertion Phase Measurement/Comparison Test Set up (Figure 10)
- b. Insertion Phase Plot (after etching process) (Figure 11)
- c. Phase Error Plot (2nd aperture excitation at 9.3 GHz) (Figure 12)
- d. Phase Error Plot (2nd aperture excitation at 9.65 GHz) (Figure 13)
- e. Phase Error Plot (2nd aperture excitation at 10 GHz) (Figure 14)

- f. Amplitude Plot (1st aperture excitation at 9.65 GHz) (Figure 15)
- g. Amplitude Plot (2nd aperture excitation at 9.3 GHz) (Figure 16)
- h. Amplitude Plot (3rd aperture excitation at 10 GHz) (Figure 17)





Figure 10. Insertion Phase Measurement/Comparison Test Setup






Figure 11. Insertion Phase Plot (After Etchi:









Figure 12. Phase Error Plot (2nd Aperture Excitation at 9.3 GHz)



Error Plot (2nd Aperture Excitation at 9.65 GHz) Phase Figure 13.



Phase Error Plot (3rd Aperture Excitation at 10 GHz) Figure 14.



Amplitude Plot (1st Aperture Excitation at 9,65 GHz) Figure 15.




Figure 16. Amplitude Plot (2nd Aperture Excitation at 9.3 GHz)




Figure 17. Amplitude Plot 3rd Aperture Excitation at 10 GHz)

2.3 Vertical Feed Line

The vertical feed line provides the single RF connection between the transmitter/receiver and the antenna. The RF input/output connection is at the lower end of the vertical feed waveguide section. Connection to the feed line is made with a short section of flexible waveguide. The vertical feed distributes the input to individual horizontal arrays by way of four-port coupling apertures into 90 degree twist sections that distribute energy to and from the 167 horizontal array sections via the diode phase shifters. The 90 degree twist sections are attached to the vertical feed line by dip brazing. The feed line and its position in the antenna assembly are shown in the photograph, Figure 18.

Vertical Feed Line Configuration. - The feed line is 120.52 inches long and is fabricated in three separate sections from precision waveguide (aluminum) per MIL-W-85/1. Waveguide dimensions are 0.400 x 0.900 inside by 0.500 x 1.00 inch outisde. See drawing 140307 for design details (available at Picatinny Arsenal).

Vertical Feed Tests. - After finalization of design detail, tests to determine actual insertion loss and VSWR were run. The results of the tests are shown graphically in Figure 19 Insertion Loss, Figure 20 VSWR (Elements 113 to 167), and Figure 21 VSWR (Expanded Figure 20).




Figure 18. Vertical Line Feed in Assembled Antenna




Figure 19. Vertical Line Feed Insertion Loss vs Frequency





Figure 20. VSWR vs Frequency: Line Feed Section #3



Frequency: Line Feed Section #3 (Expanded Scale) S VSWR Figure

2.4 90 Degree Twist Crossguide Coupler Section

Horizontal array sections are coupled to the vertical feed line (via diode phase shifters) by a 90° twist waveguide section with four port coupling apertures. A loading block is inserted in the closed end of each coupler section opposite the feed line. Four port coupling slots match apertures in the vertical feed line. Attachment of coupling sections to the feed line is by dip brazing. The physical configuration of the production section is shown in the photograph, Figure 22.

Physical Configuration. - The crosscouplers are fabricated from precision waveguide (6061-F aluminum alloy in accordance with MIL-W-85/1). Figure 23 illustrates the configuration of the part. (See drawing 140311 for dimensions, available at Picatinny Arsenal.)

Coupler Testing. - Testing this element was relatively simple because of its configuration and previous tests for terminating loads and coupling slot dimensions. VSWR tests were conducted on a sample quantity of coupling sections with results shown in Figure 24.




Figure 22. Ninety Degree Twist Crossguide Coupler in Assembled Antenna




Figure 23. Ninety Degree Twist Crossguide Section




Figure 24. Ninety Degree Twist Section VSWR Plot

2.4.1 Load: Termination (Vertical Feed Coupler). - Equalizing termination loads are required for each coupler section at the vertical feed line. The loads used in the ARBAT antenna are fabricated from ECCOSORB 17 Compound, which is molded and then machined to final dimensions. The load element is then cemented to a waveguide cap plug and the assembly is installed in the ends of each coupling section. The load element is drilled for a 4-40 screw which further secures the load/plug assembly in the coupling section. All load elements in the 167 couplers are of uniform dimensions.

Load Test. - Sample loads were tested over the operating frequency range to insure acceptable return loss values. The VSWR values obtained from the finalized design are shown in Figure 25. For detailed design including dimensions see Drawing 140313 (available at Picatinny Arsenal).




Figure 25. Load: Vertical Feed Coupler VSWR Plot

2.4.2 Phase Randomization Blocks. - Phase randomization blocks are used in the beam scanning path to reduce the degree of phase quantization effect which may occur with digital phase shifters producing relatively large phase shift increments.

The method of overcoming the possible occurrence of phase quantization effects in the ARBAT antenna is through the installation of a dielectric material block in each 90 degree twist section. The blocks are fabricated from Rexolite material in a single width $(\frac{390}{400} \text{ inch})$ and six lengths (0.216; 0.207; 0.170; 0.709; 0.722; and 0.769 inch). The phase randomization blocks are installed in the narrow dimensions of each twist section at the end adjacent to the phase shifter. Each block is held in place by a single screw and epoxy adhesive. The position of the block in the 90 degree twist section is shown in Figure 26. The configuration and dimensions for the series of blocks is shown in Figure 27.

Phase Randomization Block Tests. - The parameters of significance in the phase randomization block design are insertion phase over the radar bandwidth and return loss over the operating frequency range. The results of tests using samples of each block configuration are shown in Figure 28, Phase Randomization Block Insertion Phase vs Frequency and Figure 29, Phase Randomization Block Return Loss vs Frequency




Figure 26. Phase Randomization Block Location in Coupler




Figure 27. Phase Randomization Block Series

.400




Figure 28. Phase Randomization Block

Figure 29. Phase Randomization Block

2.5 Diode_Phase Shifter

The ARBAT antenna uses digitally controlled diode phase shifters to phase the energy radiated by the horizontal array elements in accordance with computer/software controlled logic. Phase shifter control in the ARBAT antenna permits control of the pencil beam over the range of ±35 degrees in elevation with respect to beam normal. The ARBAT antenna requires 167 phase shifters which have been supplied as Government Furnished Equipment.

The reciprocal phase shifters provide four-bit phase control over the range of 9300 to 10,000 MHz. A total of 16 phase states may be set by the logic control resulting in a phase state range of 0 to 337.5 degrees in 22.5 degree increments.

The phase shifter unit package includes a driver circuit and space for a logic decoding package. The input to each phase shifter package comes from a beam steering buffer unit. The control logic for the array (167 phase shifters) functions in a serial mode and, the decoding process is similar to signal progression through a long shift register. Each phase shifter contains two four-bit shift registers as shown in the block diagram of Figure 30. The four-bit command is clocked into the first register of phase shifter number 1 on the first shift command. A load signal transfers the four-bit command to the second register whose outputs drive the phase shifter assembly. A second shift command transfers the four-bit command to the first register of the second phase shifter where it is loaded by a load command.

The sequence described above is repeated from phase shifter to phase shifter with each decode logic assembly receiving data from the previous one (along with the bussed control commands). The output of the 167th logic assembly is fed back to the beam steering buffer for integrity verification.

The sampled output of each driver is then amplified and sent to builtin test equipment and compared to the phase-set command. A determination is made as to whether the phase shifter is receiving the correct command, and incorrect command, or if commands are reaching the unit.

The output voltages of the driver power supplies are also monitored. The outputs are compared with a predetermined reference voltage from a voltage regulator. If the output voltages vary by more than ±5 percent, an

"abnormal" condition is indicated. Phase shifter logic control organization is illustrated in Figure 30. Phase shifter position in relationship to the 90 degree twist waveguide section is shown in the assembled antenna in the photograph, Figure 31.




Figure 30. Phase Shifter Decode Logic Organization




Figure 31. Phase Shifter Position in Assembled Antenna

2.6 ARBAT Antenna Performance Monitor Concept

The purpose of the performance monitoring features incorporated into the ARBAT antenna design is to provide a dynamic checking capability on the operability and performance of the overall antenna subsystem. In addition to the latter basic function, the monitor capability facilitates the location of defective components or components operating in a degraded mode.


The performance monitoring function in the ARBAT antenna is accomplished by the inclusion of the performance monitor line and monitor line couplers described in the following section (2.6.1). The additional components required to monitor the signal detected at the output of the vertical monitor line are not parts of the antenna and are not described in this report.

In operation, overall general antenna performance may be ascertained by observing the pattern presentation on a monitor display. If the observed display is abnormal indicating degraded performance, a special diagnostic routine generated by the CPU may be initiated which supplies logic commands to the phase shifter control circuitry. By means of these diagnostic commands, the cause of the abnormal display may be localized to the individual horizontal array element and/or phase shifter in the individual array section that is responsible for the indication.


The sketches in Figure 32 (Performance Monitoring Concept) illustrate the fault detection process.

Point A of the antenna fault detection approach schematic is the location of a single ended mixer. At this point, a signal from a good antenna would be similar to the second illustration when the phase shifters are programmed through a standard scan. If the antenna has component failures affecting the elevation pattern, overall system performance will be degraded, and the sidelobe pattern will be distorted as in the third figure.


To localize the particular waveguide/phase shifter element, each phase shifter may be separately cycled linearly in phase. In a good system the amplitude waveform at point A will go through a negative zero crossing as the phase is cycled through the 90 degree phase shifter point.



Fault Detection Approach Schematic



Monitored Signal for Antenna without Failures



Monitored Signal for Antenna with Failures

Figure 32. Performance Monitoring Concept

A circuit coupled to point A, consisting of a gate seeking coincidence between a pulse generated at the negative zero crossing and another generated at the 90 degree phase instant, will provide an output if the element conditions are normal.

2.6.1 Performance Monitor Line. - The performance monitor line is connected between the last dual slot pair and the terminating load in each horizontal array section. The purpose of the performance monitor line is to collect the residual RF energy that is not radiated in each horizontal array. The residual energy is combined in the line and is detected by a diode detector connected to the lower end of the line by a coaxial line which is not a part of the antenna proper. The detected signal resulting from the combination of residual energy contributed from all elements is used to provide a dynamic check on antenna performance/status during operation.

The performance monitor line is fabricated in three separate sections using precision waveguide (0.400 \times 0.900 inch inside dimension by 0.500 \times 1.000 outside dimension) for the vertical feed line and smaller precision waveguide (0.400 \times 0.750 inch inside by 0.476 \times 0.826 inch outside dimension) for the horizontal coupling sections. The couplers, as will be noted are fabricated from the same material (type and size) as the horizontal array elements.

The coupling sections contain a milled nondirectional four port slot which couples the short horizontal sections to the vertical monitor line. Each coupling section is terminated with a matched loading block. The coupling coefficients of the sections are adjusted carefully to match the Taylor excitation generated by the vertical feed line. The coupling value is a function of slot length. The coupling values are maintained low in view of the low energy level required for the performance monitoring function.

The slot dimensions used for the 167 coupler sections in the ARBAT antenna are contained in Figure 33. Slot coupling values in voltage amplitude, coupling power ratio and coupling in dB on which the slot configurations were based are listed in Figure 34.

The performance monitor line is shown in the assembled antenna in Figure 35 and a closeup view of a section of the line shows mounting details (Figure 36).




Figure 33. Performance Monitor Slot Dimensions

"AVEGUIDE LOSSES =

0.00255 08

```
ELEMINTS = 167.
FRT = 9.65000
A = 0.70000
B = 0.40000
R = 0.40000
SPASS = 0.7
 SERPENTINE SPACING = 0.00000
                      = 0.00
POWER INTO LOAD = #AV_SUITE EUSSES =
                     0.67823
 TITAL LASSES
        AMPLITUDE (V)
0.04389 0.00193 -27.12730
0.14389 0.00193 -27.12730
                                                                        0.00223 -26.50159
                                                                                                           0.04389
                                                                                                                         0.00265 -25.76705
                                                          0.04389
                                                                                                   113
                                                                                                                         0.00265 -25.75297
0.00266 -25.73886
                                                                        0.00224 -26.49931
                                                                                                            0.04389
                                                           0.04389
                                                    58
                                                           0.04389
                                                                        0.00225 -26.47700
                                                                                                    115
                                                                                                            0.04389
                                                                                                            0.04389
                                                                        0.00225 -26.46466
          0.04387
                       0.00194 -27.11633
0.00194 -27.10533
                                                    60
                                                           0.04389
                                                           0.04389
                                                                                                            0.04389
                                                                                                                         0.00268 -25.71052
          0.04383
                                                    61
                       0.00194 -27.10543

0.00195 -27.09432

0.00195 -27.078328

0.00196 -27.07222

0.00196 -27.06114

0.00197 -27.05004
                                                                        0.00226 -26.43991
0.00227 -26.42749
0.00228 -26.41504
                                                                                                                         0.00269 -25.69629
                                                           0.04389
                                                                                                    1:8
                                                                                                            0.04389
          0.04389
                                                                                                                         0.00270 -25.68203

0.00271 -25.66772

0.00272 -25.65338
                                                                                                            0.04389
                                                           0.04389
                                                    63
                                                           0.04389
                                                                                                    120
                                                                                                           0.04389
          0.14389
                                                                        0.00225 -26.40256
                                                                                                            0.04389
                                                                                                    121
          0.04389
                                                    65
                                                           0.04383
                                                                                                                         0.00272 -25.63900
                                                                         0.00229 -26.39006
                                                                                                    122
                                                                                                            0.04389
                                                           0.04389
                                                    66
67
          0.04389
                                                                                                                         0.00273 -25.62458
                                                                        0.00230 -26.37752
0.00230 -26.36496
                                                                                                            0.04389
                        0.00197 -27.03891
                                                           0.04389
                                                                                                    123
    11
          0.04389
                                                                                                                         0.00274 -25.61011
                       0.00198 -27.02776
                                                    68
                                                           0.04389
          0.04389
                                                                        0.0231 -26.35237
0.0232 -26.3575
0.0232 -26.32710
                                                                                                                         0.00275 -25.59561
                                                           0.04389
                                                                                                    125
                                                                                                            0.04389
                                                                                                                         0.00276 -25.58107
                                                    70
71
                                                                                                    126
                                                                                                            0.04389
                        0.00107 -27.00540
                                                           0.04383
          0.04389
    14
                                                                                                            0.04389
                                                                                                                         0.00277 -25.56649
                                                           0.04389
          0.04389
                        0.00199 -26.39413
                                                                        0.00233 -26.31442
0.00234 -26.30171
0.00235 -26.28897
                                                                                                                         0.00278 - 25.55187
                        0.00200 -26.95295
                                                                                                    128
                                                                                                           0.04389
          0.04389
                                                                                                                         0.00279 -25.53721
                                                                                                            0.04389
                        0.00200 -26.97169
                                                           0.04389
                                                                                                            0.04389
                                                                                                                         0.00280 -25.52251
                                                           0.04389
          0.04389
                        0.00201 -26.96041
                                                                        0.00235 -26.27620
0.00235 -26.26340
                                                                                                                         0.00281 -25.50776
                        0.00201 -26.9-911
                                                           0.04389
                                                                                                    131
                                                                                                            0.04389
          0.04399
                                                                                                            0.04389
                                                                                                                         0.00282 -25.49297
                       0.00202 -26.93778
0.00202 -26.97643
                                                    76
77
                                                           0.04389
                                                                                                    132
          0.24387
                                                           0.04389
                                                                        0.00237 -26.25057
                                                                                                            0.04389
                                                                                                                         0.00283 - 25.47814
          0.04389
                        0.00203 -20.91500
                                                           0.04389
                                                                        0.00237 -26.23771
0.00238 -26.22482
                                                                                                    1 44
                                                                                                            0.04389
                                                                                                                         0.00284 -25.46327
          0.04391
                                                                                                                         0.00285 -25.44836
                                                                                                            0.04389
                                                                                                    135
                        0.00204 -26.90366
                                                    79
                                                           0.04389
                                                                                                                         0.00266 -25.43341
                                                                        0.0023: -26.21189
                                                                                                            0.04389
          0.04389
                        0.00204 -26.59224
                                                    80
                                                           0.04389
                                                                        0.00239 -26.19894
                        0.01205 -26.84080
                                                           0.4389
                                                                                                    1 3 7
                                                                                                            0.04389
                                                                        0.00240 -26.19596
                                                                                                                         0.00288 -25.40337
                                                                                                            0.04389
                        0.00205 -26.964933
                                                    92
                                                           0.04339
          0.04381
                                                                                                                         0.00289 -25.38828
                                                                         0.00241 -26.17294
                                                                                                    139
                                                                                                            0.04389
                        0.00205 -26.85784
          0.14389
                       0.00205 -26.65784
0.00206 -26.64633
0.00207 -26.63479
                                                                                                                         0.00290 -25.37316
                                                                        0.00242 -26.15990
                                                           0.04389
                                                                                                    140
                                                                                                            0.04389
                                                                        0.00242 -26.14682
                                                                                                                         0.00291 -25.35798
                                                    85
86
                                                           0.04389
          0.04383
                                                                        0.00243 -26.13371
0.00244 -26.12057
                        0.00207 -26.82323
                                                           0.04389
                                                                                                            0.04339
          0.64387
                                                                                                                         0.00293 -25.32751
                                                                                                            0.04389
                        n.00208 -26.91164
n.00208 -26.80003
                                                           0.04389
                                                                                                    143
                                                                                                            0.04389
                                                                                                                         0.00294 -25.31220
    32
          0.04389
                        0.00203 -26.7884C
0.00210 -26.77674
                                                                                                                         0.00295 -25.29685
                                                                        0.00245 -26.09419
                                                    УQ
                                                           0.64389
                                                                                                    145
                                                                                                            0.04389
          C.04389
    33
                                                                                                                         0.00296 -25.28145
0.00297 -25.26601
                                                                        U.00246 -26.00095
                                                    4 C
                                                           0.04389
          0.04389
                                                                        0.00247 -26.06768
                        0.00210 -26.76500
                                                           0.(4389
                                                                                                    147
                                                                                                            0.04389
          0.04389
                                                                                                                         0.00298 -25.25053
0.00299 -25.23499
                                                                                                            0.04369
          0.04389
                        0.00211 -26.75335
0.00211 -26.74162
                                                    32
                                                           0.04369
                                                                                                    148
                                                                         0.00249 -26.04103
                                                                                                    149
                                                                                                            0.04389
                                                           0.04389
    4.7
          0.04383
                                                                                                                         0.00360 -25.21941
                        0.00212 -26.72936
0.00212 -26.7180
                                                                         0.00249 -26.02766
                                                                                                            0.04389
                                                           0.04389
                                                                                                    150
                                                                        0.00250 -26.01426
0.00251 -26.00082
0.00251 -25.98735
                                                                                                                         0.00301 -25.20378
0.00302 -25.18811
0.00303 -25.17239
                                                           0.04389
                                                                                                            0.04389
          0.04381
                        0.00213 -26.70627
                                                           0.04389
                                                                                                    152
                                                                                                            0.04389
          0.0438
                        0.00214 -26.69444
                                                                                                    153
                                                                                                            0.04389
          0.04389
                                                           0.14389
                                                                                                                         0.00305 -25.15662
                                                           0.04389
                                                                         0.00252 -25.97385
                                                                                                            0.04389
           0.04389
                                                                                                                         0.00303 -25.13662
0.00306 -25.14080
0.00307 -25.12493
0.00308 -25.10902
                                                                         U.00253 -25.96030
                                                   99
                                                                                                    155
                                                                                                            0.04389
          0.04389
                        0.00215 -26.67070
                                                           0.04389
                                                                                                    156
                                                                        0.00254 -25.94673
          0.04389
                        0.00215 -26.65679
                                                           0.04389
                                                                        0.00255 -25.943312
0.00255 -25.91948
0.00255 -25.91948
0.00257 -25.90580
0.00257 -25.69207
0.00255 -25.87834
                        0.00216 -26.64586
                                                           0.04389
                                                                                                            0.04389
          0.04389
                       0.00217 -26.63490
0.00217 -26.62291
0.00218 -26.61090
                                                           0.04389
                                                                                                            0.04389
                                                                                                                         0.00307 -25.09305
           0.04399
                                                   102
103
                                                                                                    158
                                                           0.04389
                                                                                                            0.04389
                                                                                                                         0.00310 -25.07704
          0.04383
                                                                                                                         0.00311 -25.06097
0.00312 -25.04486
                                                           0.04369
                                                                                                    160
                                                                                                            0.04389
                                                           0.04389
                                                                                                            0.04389
    47
          0.04389
                        0.00219 -26.59886
                                                   1.25
                                                                                                    161
                                                                                                                         0.00314 -25.02869
0.00315 -25.01248
                                                                                                            0.04389
                                                                         0.00259 -25.86455
          0.04399
                        0.00219 -26.59679
0.00220 -26.57470
                                                   106
107
                                                           0.04389
                                                                                                    162
                                                                         0.00259 -25.55073
                                                                                                    163
                                                                                                            0.04389
          0.04389
                                                                        0.00240 -25.03688
                                                                                                                         0.00316 -24.99621
                                                                                                            0.04389
                        0.00220 -26.56259
                                                   108
                                                           0.04389
                                                                                                    154
           0.04389
                                                                        0.00241 -25.82299
0.00242 -25.80900
                                                           0.04389
                                                                                                            0.04389
                                                                                                                         0.00317 -24.97989
0.00318 -24.96352
                                                   109
                        0.00221 -26.55044
0.00221 -26.53827
                                                   110
                                                           C.C4389
                                                                                                    100
                                                                                                            0.04389
           0.04389
    54
                                                                        0.00263 -25.19509
                                                                                                            0.04389
                                                                                                                         0.00320 -24.94710
                        0.00222 -26.52607
                                                           0.04389
           0.04387
                                                   111
                                                                         0.00254 -25.78109
                        0.00223 -26.51384
                                                   112
          0.04389
                                                                                                                1 - 24
                                                                                                                            0.394(.393 - .395)
                                                                                                                25 - 45
5005-48
                                                                                                                            .390 (.389 TO .391)
                                                                                                                46 - 67
                                                                                                                68 to 91
                                                                                                                            .386 (.385 - 387)
                                                                                                                92 - 112
                                                                                                                            .382
```

Figure 34. Slot Coupling Values




Figure 35. Performance Monitor Line in Assembled Antenna




Figure 36. Performance Monitor Line (Close-Up View)

2.6.2 Loads: Performance Monitor Line. - Equalizing termination loads are required to terminate the horizontal array RF signal path, which in the ARBAT antenna is the extreme end of each coupling section attached to the performance monitor line. The performance monitor line loads are fabricated from material identical to that used for fabrication of the vertical line feed load elements, however the design and method of installation differs radically. These load elements are of uniform dimensions for all 167 elements. Oversize loads are molded from ECCOSORB 17 compound using an appropriate catalyst and milled to final dimensions. The load elements are chamfered at each edge of the surface contacting the wide dimension of the waveguide. In installation the load element is pressed into the waveguide together with a precut section of foam material the width of the load element and of a height to fully fill the space between the top of the element and the top inside wall of the waveguide above the load. The foam block holds the load firmly in place and epoxy adhesive is injected into the openings produced by the champfer at each corner of the waveguide.

For detailed design of the load element see Drawing 140325, Load, Monitor (available at Picatinny Arsenal).

Load Tests. - Tests to ascertain the return loss (VSWR) of the final load design were run throughout the antenna operating frequency range. Results of the tests are shown in Figure 37.




Figure 37. Load Block VSWR Measurement

3. TEST PROGRAM

Antenna Pattern Measurements

A major part of the ARBAT antenna development phase was the fabrication, testing, modification and retest of critical elements comprising the antenna subsystem. The procedure, which followed the paper design and computer analyses, was based on intermediate test results of single components followed by three* array range tests. On completion of these tests and after incorporation of changes determined necessary to optimize component design, a nine element test array was assembled using the optimized components. The nine element array configuration was selected as the minimum number of elements capable of producing patterns that reliably reflect the validity of the component designs, providing a confident prediction of the complete array performance.

3.1 Short Array (3 Section) Tests.

The 3 section array tests were made using a single excited horizontal array section between two "dummy" array sections positioned to provide a realistic environment for the active element. Short comb sections were used to maintain the relative positions of the three elements. The 3 section array was assembled and tested in the Van Nuys plant RF test chanber for insertion loss, VSWR (return loss) and phase error. The results of these tests are contained in the following figures. The last illustration is a computed pattern prediction based on the 3 element array phase and amplitude excitation measurements.


Figure 38. Horizontal Array Element Insertion Loss

Figure 39. Horizontal Array Element Return Loss

Figure 40. Horizontal Array Element Return Loss (Expanded D2 RL)

Figure 41. Predicted Pattern (3 Element Test)

^{*}One Excited Array and Two Dummy Arrays



Horizontal Array Element Insertion Loss (Dual Slot Radiators) Figure





Figure 39. Horizontal Array Element Return Loss (Dual Slot Radiators)



RL) D-2 Horizontal Array Element Return Loss (Expanded D2 Figure 40.




Figure 41. Predicted Pattern (3 Element Test)

3.2 Nine-Element Test Array

The nine-element range tests were designed to determine the validity of all previous tests and modifications resulting from intermediate single element testing and the three element tests in the preceding section. For the purpose of these tests it was necessary to introduce phase changes in each horizontal array input by means of small waveguide sections containing Rexolite phase shift blocks in lieu of the diode phase shifters which were not available. The phase shifting elements fabricated for these tests duplicate the electrical function of the phase shifters and insure that the results obtained are transferable to the same array if excited via the phase shifters which will be used in the operational system. Mechanically, the Rexolite block phase shift devices differed significantly from the actual diode phase shifter, as will be noted in the test array sketch, Figure 43, largely in that an "in-line" configuration was used in the test device assembly, whereas the diode phase shifters contain a 90 degree bend at the point at which the connection to the horizontal array is made. A quarter wave transformer was inserted between the phase shift test device and the horizontal array elements.

Horizontal array elements for the nine-element test array included one array element fabricated during the earlier tests in which a single array was tested singly and mounted between two ''dummy'' elements to form a three-array assembly. In order to provide a realistic electrical environment for the nine-element array, a ''dummy'' horizontal element was positioned on the outside of the first and last excited elements in the test assembly.

A short vertical feed line was fabricated for use with the test array assembly. The nine-element test array pictorial schematic is shown in Figure 42. The test array is shown mounted on a test fixture during range tests in Figure 43.

After alignment of the test array with the transmitting antenna, tests were conducted to determine elevation scan angles versus phase shift increments and azimuth patterns at beam normal, mid scan, and at scan limits. All tests were repeated at 9.3, 9.65 and 10.0 GHz.

3.2.1 Test Patterns

```
Figure 44. Nine-Element Test Array Elevation Scan Figure 45. ARBAT 9-Element Test Array Pattern Figure 46. ARBAT 9-Element Test Array Pattern Figure 47. ARBAT 9-Element Test Array Pattern Figure 48. ARBAT 9-Element Test Array Pattern Figure 49. ARBAT 9-Element Test Array Pattern Figure 50. ARBAT 9-Element Test Array Pattern Figure 51. ARBAT 9-Element Test Array Pattern Figure 52. ARBAT 9-Element Test Array Pattern Figure 53. ARBAT 9-Element Test Array Pattern Figure 54. ARBAT 9-Element Test Array Pattern Figure 54. ARBAT 9-Element Test Array Pattern Figure 54. ARBAT 9-Element Test Array Pattern
```




Figure 42. Nine-Element Test Array Assembly






Figure 43. Nine-Element Test Array Assembled

ITEM	SCAN ANGLE ELEVATION (DEG)	FREQ GHZ	Ø BLOCKS	
1	0.0	9.3	1. 0.0 2. 45 3. 67.5 4. 112.5 5. 135	6. 180 7. 225 8. 247.5 9. 292.5
2	0.0	9.65	1. 0 2. 22.5 3. 45 4. 67.5 5. 90	6. 135 7. 157.5 8. 180 9. 202.5
3	0.0	10.0	1. 0.0 2. 22.5 3. 22.5 4. 45 5. 67.5	6. 67.5 7. 90 8. 112.5 9. 112.5
4	-17.5	9.3	1. 0 2. 337.5 3. 315 4. 292.5 5. 247.5	6. 225 7. 202.5 8. 180 9. 157.5
5	-17.5	9.65	1. 0.0 2. 315 3. 292.5 4. 247.5 5. 202.5	6. 157.5 7. 135 8. 90 9. 45
6	-17.5	10.0	1. 0 2. 315 3. 270 4. 202.5 5. 157.5	6. 112.5 7. 45 8. 0 9. 315
7	-35	9.3	1. 0 2. 270 3. 202.5 4. 112.5 5. 45	6. 315 7. 225 8. 157.5 9. 67.5
8	- 35	9.65	1. 0 2. 270 3. 157.5 4. 67.5 5. 337.5	6. 247.5 7. 135 8. 45 9. 315
9	-35	10.0	1. 0 2. 247.5 3. 135 4. 22.5 5. 270	6. 157.5 7. 45 8. 292.5 9. 180

Figure 44. Nine-Element Test Array Elevation Scan



ARBAT 9-Element Test Array Pattern (Beam Normal) (9,30 GHz) Figure 45.



ARBAT 9-Element Test Array Pattern (Beam Normal) (9.65 GHz) Figure 46.







Figure 47. ARBAT 9-Element Test Array Pattern (Beam Normal) (10.0 GHz)




ARBAT 9-Element Test Array Pattern (Mid-Scan) (9.3 GHz) Figure 48.




ARBAT 9-Element Test Array Pattern (Mid-Scan) (9.65 GHz) Figure 49.




ARBAT 9-Element Test Array Pattern (Mid-Scan) (10.0 GHz) Figure 50.




ARBAT 9-Element Test Array Pattern (Scan Limit) (9.3 GHz) Figure 51.



ARBAT 9-Element Test Array Pattern (Scan Limit) (9.65 GHz) Figure 52.



ARBAT 9-Element Test Array Pattern (Scan Limit) (10.0 GHz) Figure 53.



ARBAT 9-Element Test Array Pattern (Center Element Broadside) (9.65 GHz) 54.

4. SUMMARY OF TEST RESULTS

Test results throughout the ARBAT antenna development program have been consistent with the design goals and with the performance of both component parts tested individually and as partial arrays.

Scan coverage and radiation patterns demonstrated in the nineelement test array range testing program were in accordance with the design requirement and predicted performance.

Based on extensive experience in the development of similar antenna subsystems, the results from the 9-element tests can be assumed to be reliably indicative of the full (167 element) array performance with the operational phase shifters.


APPENDIX A STRUCTURES ANALYSIS

	HAME	1 30 73	ITT Gilfillan Inc.	SHEET OF
CHECKED			THE PROJECTILE TRACKING	SKETCH NO.
APPROVED			STRUCTURES ANALYSIC	

TRAILER MOUNTED AUTENNA

DESIGN PARAMETERS

- 1. ETCROR (a) TOTAL BUDGET ETCROR (Et) = 2.0 MILLI IZADIAN
 - (b) Assumed Mechanical From Auteuna To Data Take-off = 25% of Total



(C) TRAILER & JACK SYSTEM ERROR

Z. TEMPERATURE

(a) TMAX =
$$165^{\circ}F$$
 FOUIPMENT SHALL OPERATE


TMIN = $-65^{\circ}F$

WIND LOADS 3.

(b)
$$V_6 = 75 \text{ MPH}$$
 $G_5 = .00335 V_5 = 18.85 \text{ PSF (SURVIVAL)}$

4. SHOCK
(0)
$$\Pi_{x_j}\Pi_y \notin \Pi_j = 10 g's (TRUCK TRANSPORT MODE)$$

(b) The thy = 20 fir max (RAILROAD HUMPING IMPACT)




NORMAL TRANSFORT COORDINATE SYSTEM

Z AXIS - CURBSIDE & POADSIDE

PREPARED	APO	30 73	III Gilfillan Inc.	SHEET Z OF
FALFALLE			THE PROJECTILE TRACKING	SKETCH NO.
CHECKED			RADAR	
APPROVED			STRUCTURES ANALYSIS	

5. AZIMUTH TRACKING - REQUIREMENTS

ANGULAR VELOCITY & ACCELERATION ANALYSIS



CONSIDER PROJECTILE AT ANT TIME "L"

BY DEFINITION Ro = RPCOS 45°

$$\frac{1}{126} = \frac{V_{P}t}{R_{0}}$$


$$\frac{1}{126} = \frac{V_{P}/R_{0}}{V_{P}}$$

$$\frac{1}{126} = \frac{V_{P}/R_{0}}{V_{P}}$$

$$\frac{1}{126} = \frac{V_{P}/R_{0}}{V_{P}}$$

$$\frac{1}{126} = \frac{V_{P}/R_{0}}{V_{P}}$$

$$\frac{d^2\theta}{dt^2} = \frac{-z\left(\frac{\sqrt{k}}{k}\right)^3 t}{\left[1 + \left(\frac{\sqrt{k}t}{k}\right)^2\right]^2}$$



PREPARED	APO	1 30 73	ITT Gilfillan Inc.	SHEET 3 OF
CHECKED			PROJECTILE TRACKING	SKETCH NO.
APPROVED			STELETURES ANALYSIS	

AZIMUTH TRACKING

ANGULAR VELOCITY & ACCELERATION (CONT. P)

SOLVE FOR INITIAL STARTING TIME L: @ 0=450

:.
$$tau45^{\circ} = 1.0 = \frac{V_{p}t_{i}}{R_{o}}$$

 $t_{i} = \frac{R_{o}}{V_{p}} = \frac{R_{p}cos45^{\circ}}{V_{p}}$ Let $R_{p}=1500 \text{ m}$
 $= \frac{1500 \times .707}{1000}$
 $t_{i} = 1.06 \text{ Sec.}$

PER P 2.1 REQUIREMENTS

WITH ELECTRONIC 5-AN @ ± 3.5°/SEC.

SOLVE FOR MINIMUM RP TO SATISFY BOTH CONDITION

$$\frac{1}{\theta} = \frac{V_{P}}{ZR_{O}\cos 4I_{O}} = 0.70 \quad EAD/SEC.$$

SOWE EDW (3) FOR RP FOR 0 = 0.70 PAD/SECT-

$$\dot{\theta} = \frac{-2 \left(\frac{V_p}{R_p \cos u} \right)^2 + i}{\left[1 + \left(\frac{V_p t_i}{R_p \cos u} \right)^2 \right]^2} = 0.70$$

PREPARED	APO NAME	1 30 73	III Gilfillan Inc.	SHEET 4 OF
			THE PROJECTILE TRACKING	SKETCH NO.
CHECKED			KADAIZ	
			STRUCTURES ANALYSIS	
APPROVED				

MIENNA SYSTEM

INTRODUCTION :

THE ANTENNA SICSTEM WILL BE MOUNTED ON A VEHICLE BED WITH JACK PAD PROVISIONS TO LIFT THE ENTIRE OR PORTION OF THE SPRUNG MASS OF THE VEHICLE-ANTENNA SYSTEM. THE ANTENNA WILL BE OF NERRY WITH PHASE SHIFTER TYPE DESIGN ATTACHED TO A CENTER MAIN STRONG BACK STRUCTURE WHICH SERVES AS A TORQUE TUBE AS WELL AS A CANTILEVER BORM FOR ELEVATION BENDING MOMENT, THE ANTENNA WILL HAVE A MAXIMUM TILT OF 250 WITH THE VERTICAL ANS. THE TRANSCEIVER 'ASSEMBLY WILL BE MOUNTED TO THE MAIN BACK STRUCTURE SO POSITIONED FOR MINIMUM MASS MUMENT OF INERTIA EFFECT ABOUT THE AZIMUTHAL AYS.

THE ANTENNA SYSTEM WILL BE ASSEMBLED TO A PEDESTAL WHICH HOUSES THE BULL GEAR - BEARING ASSEMBLY, DRIVE MOTOR, GEAR BUY & DATA TAKE OFF, EXISTING AN/SPS-48 PEDESTAL CAN BASILY BE ADAPTED IN THIS DESIGN, THE PEDESTAL IN TURN IS PERMANENTLY BOLTED TO THE TRAILER BED. THE TRAILER IN THE JACKED POSITION SHALL BE SO DESIGNED TO ACT AS NEARLY RIGID FOR SUDDENLY APPLIED TORSIONAL LOAD AT THE PEDESTAL BASE, THE JACK-PADS WILL REST ON A PREPARED ON-SITE GROUND FOOTINGS THE 8 HOURS SET UP PINE CAN BE ACHIEVED. THE JACK ASSEMBLY LATERAL DETLETION (WHICH INCLUDES ANY ATTACHMENT TO THE TRAILER BODY) SHALL BE HELD TO AN ACCEPTABLE LIMIT UNDER OPERATING CONDITION.

	A FO	1 30 73	ITT Gilfillan Inc.	SHEET 5 OF
PREPARED			THE PROJECTILE TRACKING	SKETCH NO.
APPROVED			STRUCTURES AVALYSE	

VITENNY EXELEN MEIGHTS

WEIGHT ANALYSIS - X' BAILD RADAR

COMPONENTS


(1)	BASIC WIG. ARRAYS 2004 FT @ 12#/FT	=	240 LBS	5
(Z)	W.G. FLANGES (167) & HARDWARES		30 LBS	
(3)	PHASE SHIFTERS (167 @ 19# BA)	-	150 LBS	5
(4)	LINE FEED WIG. + BENT TRANSITION	=	Z5 LB	S
•	BUFFER BEAM, STEERING	=	25 48	S
	bomes subbra	=	50 LB	S
(7)	CABLE, BUS BAR, DBIYDRATOR, ETC.	=	30 rs	S
(8)	TRANSCEIVER ASSY	=	375 LB	5
(9)	and a second sec	=	15 LB	S
	SUB-TOTAL()	=	940 LB	ร

STRUCTURES & HOUSINGS

(1) USING AN/SPS-48 PEDESTAL (ROTATING MASS ONLY) (a) TOP PLATE ADAPTER (D=46.01), D=24.011) + CLEVISES (b) INNER BEG RACE A=50112 Day=37.011) =	170	LBS LBS
SUB-TOTAL (2)	=	Z90	LBS
(Z) PHASE SHIFTER HOUSING TRANSITION PLATE (3) COMPONENT ITEMS (S) & & (T) HOUSING	=======================================	50 20	Les Les
(4) CEUTER MAIN TORQUE-BOX BEAM TUBE t=0.28, 240 x 32.0	=	350	rbe?
(5) TRUSS MEMBERS Z75 FT @131 #/FT	=	360	LBS
(6) 10 TON ACTUATOR #1810	=	60	re2
SUB-POTAL (3)	Ξ	840	LBS


TOTAL WEIGHT = 2070 LBS

PREPARED	4PO	130 73	III Gilfillan Inc.	SHEET 6 OF
CHECKED			PROJECTILE TRACKING	SKETCH NO.
APPROVED			STRUCTURES ANALYSIS	



	JAP	133/73	TTT Gilfillan Inc.	SHEET OF
PREPARED		1313	THE PROJECTILE TRACKING	SKETCH NO.
CHECKED		 	STRUCTURES DUALYSIS	

MASS DISTIRIBUTION ANALYSIS (CONT'D)



PLAN VIEW - MASS DISTRIBUTION

$$\overline{X} = \frac{-745 \times 60 - 25 \times 46 + 240 \times 18 + 360 \times 30 + 125 \times 22.0}{2070} = \frac{2020}{2070} = \frac{0.97 \text{ IN}}{20}$$


$$\overline{Z} = \frac{245 \times 27.0 + 25 \times 10 + 240 \times 76.0 + 350 \times 120 + 360 \times 14 + 125 \times 12.0 - 375 \times 7.0 - 60 \times 12.0}{2070} = \frac{19270}{2070} = \frac{9.30 \text{ IN}}{2070}$$

$$I_{m})_{YY} = \frac{1}{37.2} \left[245 (639)^{2} + 25 (47)^{2} + 60 (17.0)^{2} + 375 (7.0)^{2} + 350 (12)^{2} + 290 (18)^{2} + 125 (25)^{2} + \frac{360 (144)^{2} + 360 (33)^{2} + \frac{240}{12} (150)^{2} + 240 (31.5)^{2} \right] \frac{1}{144} = \frac{3.012 \times 10^{6}}{32.2 \times 144}$$

PREPARED	APO.	13173	III Gilfillan Inc.	SHEET 8 OF
CHECKED			THE PENJECTILE TRACKING	SKETCH NO.
APPROVED			STRUCTURES ANALYSIE	

STRUCTURES ANALYSIS

CAOL GUILL



TORUJE LOAD

Tul = 590.0 FT-#

TORQUE BOX-BEAM ANALYSIS


TOTAL TORQUE LOAD ON TUBE

TT = 1045.0 FT - MAXIMUM TORQUE RED'D, AT AUTENMA

TORSIONAL STIFFNESS (K) OF TUBE

$$K = \frac{2t b^2 a^2}{(a+b)} = \frac{21.25(24)^2(32)^2}{(24+32)}$$

K = 5266.0 14



PREPARED	APP	1)31/73	ITT Gilfillan Inc.	SHEET 9 OF
PREPARED			THE PROJECTILE TRACKING	SKETCH NO.
CHECKED		<u> </u>	ETRUCTURES ANALYSIS	

TORQUE BOX-BEAM ANAUTSIS (CONT'D)

SOLUE FOR AMERICAR TUDIST "Oft"

Ett = Att = 0.075 ×10 RAD = 0.075 M.R. « Ett = .125 OK

BENDING DEFLECTION & ROTATION OF TOBE

AT 30 MPH WIND

CONSIDER TUBE CANTILEVERED & B(B)


UNIFORMLY LOADED

W=Fo=410*

$$\Delta_{\tau} = \frac{WL^{3}}{8EI_{W}} = \frac{410(120)^{3}}{8WJ^{7}k2800}$$

AT = 0.0032 IN

AUGULAR ROTATION Ab



$$I_{xx} = \frac{1}{12} \left[\overline{24}^3 \times 37 - \overline{23} \times 31.5 \right]$$

$$I_{xx} = 2800 \text{ IM}^4$$

TILTING SCREW ACTUATOR ANALYSIS

THE ACTUATOR WILL BE A DUFF-NORTON SCREW ACTUATOR MODEL # 1810 ARTED AT 10 TON, THE LIFTING SCREW IS A ZIOD INCH DIA, WITH A . SO INCH PITCH SOUNCE THREAD. THE ERECTED LEWATH OF THE SCREW IS

CALCULATE LOADS ON ACTUATOR & TRUUNIONS

PREPARED NAME CHECKED	THE PROJECTILE		SHEET OF SKETCH NO.
APPROVED		ANALYSIS	
ANTENNA TRUNNIC	ON PIVOT & ACTUATOR AND		
(A) WIND LOAD (ERECT CONDITION)		qa	75
EMRP =0 60F0+ 1770×6 PACT)=(60×6	7=32.0 [20.0 PACT)0 (20.0+17.3)] HO H720x6.7) 26.44	60.C - 6.7 //	

SURVIVAL COUDITION

PACT) S = (60×3070+1720×6.7)(26.40)

Prot) = 1500 LBS

RAIL ROAD IMPACT LOAD $\Pi_3 = \Pi_4 = 20 \, \xi^{1/3}$ (250 TILT) $\Pi_3 = 20 \, \xi^{1/3} \quad \text{Tact} = 0.0$ $RP = \frac{\text{Wh} \times 51 \, (\Pi_3)}{24.0} = \frac{1720 \times 51 \times 20}{24.0} = \frac{73,000 \, \text{LBS}}{24.0}$


* BASED ON THESE CALCULATED LOADS ON TRUNNION SACTUATOR, STOWAGE BASE ARE RECONTRED DURING RAIL ROAD SHIPMENT OF ANTONIA ASSEMBLY.


	ATT	13173	ITT Gilfillan Inc.	SHEET OF
PREPARED		1 1 9	THE PROJECTILE TRACKING	SKETCH NO.
CHECKED			SACIA	
APPROVED			STRUCTURES ANALYSIS	L

SCREW ACTUATOR ELONGATION OR CONTRACTION

ACTUATION SCREW, SOURCE THEORY

Do = 2.00 IN
Dr = 1.612 IN
Leff = 19.5 IN
E = 29 NO 6 PEI
PACT) = 1500 LBS
AR =
$$\frac{\pi}{4}(1.612)^2 = 7.05 IN^2$$






$$E_{ACT} = \frac{\Delta_{ACT}}{5} = \frac{.00048}{72.5} = 0.02 \text{ M.R}$$

CHECK BUCKLING $\frac{P_{CR}}{P_{CR}} = \frac{1.612/4 = 1.403}{4 \cdot \frac{1.612}{403}} = \frac{1.612/4 = 1.403}{4 \cdot \frac$

$$\frac{P_{ce}}{4(\frac{403}{403})^2} = \frac{(3.14) \times 29 \times 10^6 \times 2.05}{4(\frac{403}{403})^2} = \frac{62,600 \text{ LBS}}{62,600 \text{ LBS}} = \frac{62}{62}$$


BEARING ANGULAR ROTATION (ELEV) (EBRG)

PREPARED	NAME J Zo=	7/25/23	ITT Gilfillan Inc.	SHEET 12 OF
CHECKED	~		THE ARBAT COMBINED STRUCTURAL LOADING	SKETCH NO.
APPROVED			STEDCIORAL ZEAUNZE	////SL ~



FORM 118 - (5-67)

PREPARED	S. E.E	7/25/73	ITT Gilfillan Inc.	SHEET 13 OF
CHECKED			COMPUTER MODEL FOR	SKETCH NO. PHASE 13
APPROVED			STRUPAK ANALYSIS	TANJE 2




STRUPAK PROGRAM ZDTSAP

P4 = 16.5+15.6 = 30.1 16

DEFLECTION RESULTS

A, = .000979 W


EH = .000979 x1000 = .025 Mr



ASSUME CENTER SECTION TORQUE BOX TO

BE RIGHT & DEFLECTIONS ARE DUE TO BENDING

OF TRUSS STRUCTURE ONLY



FORM 118 - (5-67)

PREPARED	100 NAME	2 1 73	III Gilfillan Inc.	SHEET \5 OF
			THE PROJECTILE TRACKING	SKETCH NO.
CHECKED			SACAST	
APPROVED			STRUCTURES ANALYSIS_	


STRUCTURES ANALYSIS ANTENNA VEHICLE

INTRODUCTION:

THE ANTEUNA - PEDESTAL ASSEMBLY WEIGHING APPROX, 3000 LES WILL BE MOUNTED BIGIDLY TO THE CENTER TRAILER CHASSIS AS SHOWN BELOW, FOUR (4) MAIN JACKS WILL RAISE THE SPRUNG MASS OF THE AUTENINA VEHICLE ASSEMBLY .. A FIFTH JACK FOR MODED STABILITY IS LOCATED AT AT THE TAIL OUD OF TRAILER.

THE DESIGN CRITERIA IS A ROTATIONAL OR A BENDING MOTALVED SAJUBUA

Eith = 0.75 MILLIRADIAN (REF. SHT 1)



PREPARED	APD	2/1/73	ITT Gilfillan Inc.	SHEET 16 OF
CHECKED			PROJECTILE TRACKING	SKETCH NO.
APPROVED			STRUCTURES ANALYSIS	


ANTENNA-VEHICLE STRUCTURES ANALYSIS (CONT'D)

ANALYSIS PARAMETURS


$$q_0 = 2.52 \text{ PSF} @ 30 \text{ MPH} (OPERATION)$$
 $q_5 = 18.85 \text{ PSF} @ 75 \text{ MPH} (SURVIVAL)$
 $C_0 = 1.30$
 $A_{MJ} = 175 \text{ FT}^2$
 $F_0 = C_0 q_0 A = 1.30 \times 2.52 \times 125$
 $F_0 = 410 \text{ LBS}$
 $F_5 = C_0 7_5 A = 1.30 \times 18.85 \times 125$

CHASSIS TRANSVERSE BEAM STIFFLESS DETERMINIATION)

USE AISC 6.0x3.0 RECT. TUBING = 3/8



$$\int_{b} = \frac{M\dot{c}}{I_{N}} = \frac{147,400 \text{ N}-1}{22.7}$$




PREPARED	LPD	2 1 73	ITT Gilfillan Inc.	SHEET A OF
			THE PROJECTILE TRACKING	SKETCH NO.
CHECKED			RADAR	
APPROVED			STRUCTURES ANALYSIS	

FRONT TRUNUION PIVOT ANDLYSIS

THE TRUNIOUS ARE BESIGNED FOR LOADS UNDER RAILROAD IMPACT LOAD. THE LOAD PER TRUNNIONS (REF. SHORT 10) WAS PREVIOUSLY CALCULATED TO BE


PRE-LIMIUAR' C DESIGN

LET DP = 1.50 IN BASIC PIN DIAMETER NAS
LETT = 2.00 IN BRG. LENGTY R.



BEARING STREES

For 6061-T6 CLEVIS BLOCK




BENDING STRESS ON BOLT

LOAD ON ZOO IN SPAN 1/2/10 BOLT

$$S_b = \frac{17D_b}{32.0} = \frac{3.14(1.25)^3}{32.0}$$

 $S_b = 0.1921N^3$



DIA, BOLT WITH

ADJUSTABLE BUSHINGS.

FORM 118 - (5-67)


PREPARED	APD APD	2/1/73	ITT Gilfillan Inc.	SHEET 17 OF
CHECKED			PROJECTILE TISACKING	SKETCH NO.
APPROVED			STRUCTURES ANALYSIS	

ANTENNA - VEHICLE STRUCTURES AWALYSIS

CHASSIS TRAUSVERSE BEAM (CONTO)

INCLUDE DL = 30004/2 = 15004 ASSUMED CONC. AT CENTER

$$M_{DL} = 1500 \times 84/4 = 31,500 \text{ IN-4}$$
 $M_{LL} = F_S e_{C/Z} = 147,000 \text{ IN-4}$
 $M_{T} = 178,500 \text{ IN-4}$
 $M_{T} = 178,500 \times 3.0$
 $M_{X} = 7_{XX} =$



DYNAMIC LORDING ON PRAME

FUR FIS = 1.50,
$$\sqrt{16}$$
 $m_{L} = \frac{36,000}{1.5} = 24,000$

Thug = $\frac{315,000 \times 3.0}{24,00} = \frac{39.4 \times 40}{100}$

The Girls of the G.0"sa TUBING

 $\sqrt{160} = \frac{315,000 \times 3.0}{24,000} = \frac{39.4 \times 40}{100}$
 $\sqrt{160} = \frac{36,000}{100} = \frac{39.4 \times 40}{100}$
 $\sqrt{160} = \frac{36,000}{100} = \frac{39.4 \times 40}{100}$
 $\sqrt{160} = \frac{36,000}{100} = \frac{36,000}{100} = 24,000$
 $\sqrt{160} = \frac{36,000}{100} = 24,000$
 $\sqrt{1$


$$\frac{\text{(Ett)} = \frac{M_0 L}{12 E I} = \frac{19680 \times 84}{12 \times 40.5 \times 30 \times 106} = .000 \text{(I3 RAD)}$$

$$\frac{\text{(ELEVATION DIRECTION)}}{\text{(ELEVATION DIRECTION)}} = 6.0$$

FORM 118 - (5-67)

PREPARED	NAME	2 1 73	III Gilfillan Inc.	SHEET 18 OF
			THE PROJECTILE TRACKING	SKETCH NO.
CHECKED			STRUCTURES ANDLYSIS	

JACIE STEJETURE TORSIONAL & BENDING FORTION



JACK SHEAR REACTION (FIH) (OFFSATING CONDITION)

CHASSIS TRANSUERSE BEAM (A-B) WAS PREVIOUSLY SIZED TO BE 6x6 x 3/8 , AISC TURING.


SOLVE FOR TORSIONAL STIFFNESS OF LENGTH (Lih)

$$0=6.00 \text{ IN } \text{ K}_{5}=0^{3}t=6^{3}x\frac{3}{8}$$
 $t=\frac{3}{8}$ IN $t=\frac{81.00 \text{ IN }^{4}}{2}$ POLAR MOMENT OF INERTA

PREPARED	HAME APD	2/1/73	ITT Gilfillan Inc.	SHEET 19 OF
CHECKED			PROJECTILE TEACKING	SKETCH NO.
APPROVED			STRUCTURES ANALYSIS	

JACK STRUCTURES TORSIONAL & BEILDING ROTATION (CONT'D)

CONSIDER ONE JACK SUPPORT



FROM THE ABOUE RESULTS A DAMETRAL CLEARANCE (SLOP) OF THE JACK CAU BE TOLERATED TO A MAXIMUM OF

PREPARED	APD CPA	Z 1 73	ITT Gilfillan Inc.	SHEET ZO OF
			THE PROJECTILE TRACKING	SKETCH NO.
CHECKED			RADAR	
APPROVED			STRUCTURES ANALYSIS	

ANTENNA-VEHICLE SYSTEM STABILITY - SURVIVAL COND.

PEFERRING TO SKETCH ON PILL AUD LOAD IS ON PIE AND TAKING MOMENT ABOUT (P-P)

RESTRAINING MOMENT (RM)

= 13,000 x42

RM = 546,600 IN-# = 45,500 FT-#

OUBSTURNING MOMENT - (OM)

OM = FS x EP

= 3070 x 120

OM = 368,400 11-# = 30,700 FT-#

$$\frac{PM}{OM} = \frac{546,000}{368,400} = 1.48$$

FOR A 13,000 LB AUTENUA-VEHICLE WEIGHT THE SYSTEM THEREFORE IS STABLE AND NEEDS HO EXTERNAL STOWAGE PROVISION.

PREPARED	HAME APD	2/1/73	IIT Gilfillan Inc.	SHEET Z OF
			PROJECTILE TRACKING	SKETCH NO.
CHECKED			STRUCTURES ANALYSIS	

Fs=3070

JACK PAD BEFRING LOAD FWANTSIS

* USE BURUIVAL LOAD (FS) ON AUTEUNA ZMR =0

$$R_{2} = \frac{F_{5} C_{p}}{2L} - \frac{W_{+}}{4}$$

$$= \frac{3070 \times 120}{Z \times 84} - \frac{13,000}{4}$$

$$= 2190 - 3250$$

R2=-1060 LBS COMPRESSION ON SOIL CP=1700

ZMP, = 0

R, =-2190 -3250

R = - 5440 LBS (COMPRESSION)

DESIGN JACK PAO FOOT PRINT BOSEING LOAD OF * Page = 5000 LBS

* DESIGN JACK FOR STON OR 10,000 LAS CAPACITY,

FWF= 13 000 #

ASSUMPTION

OURSE MODILIES OF SUBFRAUE REACTION KU = 100 PSI/IN ALLOW THE SYSTEM TO OPERATE ON SOIL SUCH AS SOFT CLAY, CLAY LOAM POORLY COMPACTED SAND, CLAY CONTAINING LARGE AMOUNT OF SILT & WATER STANDS DURING WET SEASON!

$$A_{PAD} = \frac{P_{BYR}}{F_{BRCI)AL}} = \frac{5000}{1500} = 3.33 f7^{2}$$

$$D_{PAD} = \frac{4 \times 3.3}{11} = 2.06 f7 \text{ OR } (D_{PAD} = 24.00 \text{ IN})$$
THE DIFFERENTIAL BEARING LIVE LOAD $\Delta P_{LL} = 2190 \text{ LBS}$

- L= 84.0

:
$$\Delta_{DIFF} = \frac{\Delta_{LL}/\Delta_{PAD}}{K_{U}} = \frac{2190/(3.14 \times 144)}{100} = 0.048 \text{ IN}$$

$$\frac{E_{PAD}}{E_{PAD}} = \frac{\Delta_{DIFF}}{L} \times 1000 = \frac{.0480}{840} \times 1000$$

$$\frac{E_{PAD}}{E_{PAD}} = 0.570 \text{ MILLI RADIAN}$$

FORM 118 - (5-67)

PREPARED	B, ROE	10/5/76	177 <u>Gil</u> fillan	SHEET / OF /
CHECKED			PHASE B ANTENNA	SKETCH NO.
APPROVED			WEIGHTS	

ANTENNA STRUCTURE	722.0
LINE FEED	45.5
ARRAYS (167)	235.5
MONITOR LINE	22.4
PHASE SHIFTERS (167)	167.0
PHASE SHIFTER HOUSING	45.3
COM BS	26.0
	1263.7 16

WEIGHT OF ANTENNA SYSTEM DESIGNED &

FABRICATED UNDER PHASE B. THESE WEIGHTS

WILL BE UTILIZED IN PHASE C FOR

ANALYSIS & DESIGN OF SERVE SRIVE SYSTEM.

REPORT DISTRIBUTION

Final	
Tech Report DI-S-180	
Commander Picatinny Arsenal ATTN: Technical Support Directorate	
SARPA-TS-T-S 5 SARPA-TS-1 1	
Product Assurance Directorate 10 SARPA-QA-A-R Dover, New Jersey 07801	
Project Manager Munitions Prod Base Mod & Exp Picatinny Arsenal	
ATTN: DRCPM-PBM 1 Dover, New Jersey 07801	
Defense Documentation Center Cameron Station Alexandria, Virginia 22314 12	
Commander U. S. Army Material Development & Readiness Command ATTN:	
DRCRD-WC 1 DRCRD-OS 1 DRCQA-E 1 Washington, D. C. 20315	
Commander	
U. S. Army Armament Command ATTN: DRSAR-QAE 3 DRSAR-RD 1 DRSAR-AS 1 Rock Island, Illinois 61201	

Commander U. S. Army Electronics Command ATTN: DRSEL-CT-R Fort Monmouth, N.J. 07703	3
Commander U. S. Army Test & Eval. Command ATTN: DRSTE-RU Aberdeen, Maryland 21005	1
Commander U. S. Army Missile Command ATTN: Technical Library Redstone Arsenal, Alabama 35809	1
Commander Ballistic Research Laboratories ATTN: Technical Library Aberdeen Proving Ground Maryland 21005	1
Commander Harry Diamond Laboratories	
ATTN: DRXDO-TA Washington, D. C. 20438	1
DRXDO-TA	1
DRXDO-TA Washington, D. C. 20438 Commander Frankford Arsenal ATTN: N3200	

Commander	
White Sands Missile Range	
ATTN:	1
reclificar biblary	1
New Mexico 88002	
Commander	
Jefferson Proving Ground	
ATTN:	
STEJP-MTM	1
Madison, Indiana 47521	
Commander	
Naval Ordnance Systems Command	
ATTN:	
Code ORD-0462D	1
Washington, D. C. 20362	
Director	
Naval Research Laboratories	
ATTN:	7
Technical Library	1
Washington, D. C. 20390	
Commander	
U. S. Naval Weapons Laboratory	
ATTN:	
Technical Library	1
Dahlgren, Virginia 22488	
Commander	
U. S. Naval Ordnance Test Station	
ATTN:	_
Technical Library	1
China Lake, California 93555	
Commander Marine Corps	
Hq., U. S. Marine Corps	
ATTN: Code A04C	1
Washington, D. C. 20380	-
washington, b. d. 2000	
Commander	
Wright Air Development Division	
Wright-Patterson Air Force Base	
ATTN:	
Technical Library]
Ohio 45433	

Commander	
Rome Air Development Command	
Griffiss Air Force Base	
ATTN:	
Technical Library	1
New York 13440	
Commander	
Air Force Rocket Propulsion Lab (AFSC)	
ATTN:	
Mr. L. Meyers (RPMMA)	1
Edwards Air Force Base	
California 93523	
Commander	
ADTC (ADLEG)	
ATTN:	
Mr. J. Howanick]
Eglin Air Force Base	
Florida 32542	
Commander	
Service Engineering Division (MME)	
ATTN:	
Mr. D. Hebdon (MMECL)	1
Hill Air Force Base, Utah 84401	

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

REPORT DOCUMENTATION	READ INSTRUCTIONS BEFORE COMPLETING FORM			
1. REPORT NUMBER	2. GOVT ACCESSION NO	3. RECIPIENT'S CATALOG NUMBER		
4. TITLE (und Subtitle)	1	5. TYPE OF REPORT & PERIOD COVERED		
MM&TE-Application Of Radar To Ball tance Testing of Ammunition (ARBA)	Final Report			
Phase B: Antenna Development/Fabr	6. PERFORMING ORG. REPORT NUMBER			
rnase B. Antenna Development, rabb	5059			
7. AUTHOR(s)		8. CONTRACT OR GRANT NUMBER(s)		
C. Barfield		DAAA21-73-C-0664		
9. PERFORMING ORGANIZATION NAME AND ADDRESS		10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS		
International Telephone & Telegra	ph Corporation			
Gilfillan Division	01/00	MM&TE Project 5704139		
7821 Orion Street, Van Nuys, CA.	91409	10		
11. CONTROLLING OFFICE NAME AND ADDRESS		30 September 1976		
Picatinny Arsenal, Dover, N.J. 0	7801	13. NUMBER OF PAGES		
14. MONITORING AGENCY NAME & ADDRESS(II differen	nt from Controlling Office)	15. SECURITY CLASS. (of this report)		
		Unclassified		
		15a. DECLASSIFICATION/DOWNGRADING		
		SCHEDULE N/A		
16. DISTRIBUTION STATEMENT (of this Report)				
Unlimited				
17. DISTRIBUTION STATEMENT (of the abstract entered	in Block 20, if different i	rom Report)		
77. DISTRIBUTION STATEMENT (STATEMENT)				
18. SUPPLEMENTARY NOTES				
19. KEY WORDS (Continue on reverse side if necessary as				
Ammunition Testing		a Performance Monitor		
Ballistic Trajectory	requency/Mechanical Scanning			
Electronic Elevation Scanning	delobe Amplitude			
Dual Slot Radiators	Array Antenna			
Projectile Tracking Radar 20. ABSTRACT (Continue on reverse side if necessary and	d identify by block numbe	()		
Antenna design analyses performed in an earlier program phase (ARBAT System				
Design Study) were validated and used in the final development and fab-				
rication of an "X" band phase/frequency mechanical scanning radar antenna to				
be incorporated in a radar system for ballistic ammunition acceptance testing.				
The antenna is a 10 by 12 ft aperture planar array. Elevation scanning is accomplished by phase changes produced by digitally controlled 4 bit diode				
phase shifters. Scanning in azim	arn is by itedue	ency variation and mechanical		

DD 1 DAN 73 1473 EDITION OF 1 NOV 65 IS OBSOLETE

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (Phen Date Entering)

Block No. 20 (Continued)

rotation of the array. Development steps included fabrication and testing of individual critical items and assemblies of critical items to estimate full array performance. A 9 element partial array was range tested prior to fabrication of the required 167 horizontal array elements and associated microwave elements. The mechanical and electrical design is discussed and test results are summarized.